

### **Nassau County Notes:**

1. County Permit is required to construct curbs / sidewalks.
2. Replace all non-approved curb cuts with Standard County curb (Type C), repair all uplifted, depressed, cracked or missing sidewalks, curb(s), and all non-ADA compliant ramps.
3. Refurbish all Pavement Markings that have been removed / damaged during construction, (including but not limited to edge lines, hatching, etc.) according to Nassau County Specification.
4. **Use of Regulatory Signs and/or Turn Restrictions and/or Parking Restrictions on Site Plans shall be placed / installed according to the latest “National Manual On Uniform Traffic Control Devices” (MUTCD) and the “New York State Supplement,” and the applicant shall have these signs *Ordinanced by the respective Town/Village/City.***
5. If Nassau County has signs that have been removed / damaged during construction, (including but not limited to regulatory signs, warning signs, etc.) they shall be installed / replaced according to Nassau County Specification.
6. If any Nassau County traffic equipment at the location, (including but not limited to traffic signals, pedestrian signal equipment, traffic loop wire detection, traffic pullboxes, traffic signal system interconnect, street lighting, etc.), is damaged in any way during construction, it shall be repaired / replaced according to Nassau County Specification. All work shall be performed by a Nassau County Approved Traffic Signal Contractor. The Contractor shall notify *Sheila M. Dukacz of the Nassau County Traffic Signal and Construction Operations Unit at 516-572-0465 ext. 20958* before any work begins.
7. The Contractor shall regrade any Nassau County traffic signal pullbox covers in the work area using suitable brick and mortar. The Contractor shall leave the inside bottom of all pullboxes clean and free of debris left from his operations. The tops of the covers shall be left clean and free of concrete. If any pullbox work is required, the Contractor must notify *Sheila M. Dukacz of the Nassau County Traffic Signal and Construction Operations Unit at 516-572-0465 ext. 20958* in advance of the work.
8. The Contractor shall have any Nassau County traffic loop replaced if scheduled to be damaged during construction. The Contractor must have an approved Traffic Signal Contractor place the signal in recall operation in advance of the work that will damage the loop detector. The new loop must be replaced immediately by an approved Traffic Signal Contractor after the area is restored. The size and placement of the new loop will be determined by Nassau County. A Nassau County Inspector must be present upon replacement. The Contractor must notify *Sheila M. Dukacz of the Nassau County Traffic Signal Construction and Operations Unit at 516-572-0465 ext. 20958* in advance of the work.
9. Prior to construction, a mark-out shall be made for all underground utilities, including but not limited to underground traffic signal equipment.
10. Prior to any scheduled lane closures, the contractor must complete and submit an online road/lane closure notification form by 3:00 PM the evening prior to the scheduled closure. The contractor can complete the form at [www.nassaucountyny.gov/trafficmanagement](http://www.nassaucountyny.gov/trafficmanagement), or by faxing the completed form to the Traffic Management Center at (516) 571-6882.
11. If required handicap ramp work impacts any utilities in any way, including relocation, the appropriate utility company shall be notified prior to handicap ramp work beginning.